



30 Things Wrong With This Renovation

1. leaking skylight (installed flat)
2. water damage from leaking roof, potential for mold
3. upper cabinet crown molding installed over recessed light
4. broken recessed light
5. cracked drywall at top left corner of door, resulting from poor foundation
6. hinge installed, but cabinet door missing
7. cabinet doors falling off — poor installation
8. door installed backwards, door handle likely to cause damage to counter and dishwasher
9. door not properly sealed, some foam showing, trim missing
10. outlet installed over cooktop
11. there's no GFI for the kitchen circuit
12. outlet too high for refrigerator
13. refrigerator installed in front of a window
14. cooktop is not vented
15. register not in the proper place
16. heat register not in the proper place
17. wood floor buckling
18. window unfinished, some foam showing, trim missing
19. unfinished wooden window above the sink, likely to cause wood damage
20. no smoke detector
21. no backsplash behind sink
22. mismatched cabinet handles
23. mismatched cabinet handles
24. countertop in two pieces and not installed flush, eventual water damage likely with sink so close to seam
25. no baseboard on the back wall
26. dishwasher should ideally be near sink and less exposed
27. unfinished wood cabinet
28. missing cabinet door
29. missing cabinet door
30. no CO detector (plug-in or otherwise)